




User Guide

Capacity controller with heat recovery AK-PC 781

ADAP-KOOL® Refrigeration control systems






Menu list

This menu function can be used together with system software type AKM. The description is divided up into function groups that can be displayed on the PC screen. Within each group it is now possible to show the measured values, or settings. Regarding the use of AKM, reference is made to the AKM Manual.

Validity

This menu operation (from March 2013) applies to controller type AK-PC 781, code number 080Z0186 / 080Z0187 / 080Z0188 / 080Z0189 / 080Z0190 with programme version 4.1x.


Function groups



The operation is divided up into several function groups. When a selection has been made, push "OK", and you may continue to the next display. By way of example, "Suction capacity control" has been selected here.

From the measure line the different values can be read. The values are constantly updated.

In the list of settings the set values can be seen. If a setting has to be changed, select the parameter and proceed via "OK".



Measurements

The various measurements can be read directly. If a graphic display of the measurements is required, up to eight of them can be shown. Select the required measurements and push "Trend".

Settings

Settings can only be made for the daily operation. Configuration settings cannot be seen, changed or written out. They can only be made from the Service Tool programme.

There are four kinds of settings, ON/OFF settings, settings with a variable value, time settings and "reset alarms".







Enter the new value or move the sliding scale up or down. The new value will apply, when "OK" is pushed.




Go through the individual functions one by one and make the required settings. When settings have been made for one controller, the set values may be used as basis in the other controllers of the same type and with the same software version. Copy the settings by using the copy settings function in the AKM programme, and adjust subsequently any settings where there are deviations.

NB! If a list is required for noting down the individual settings, a printout can be made of it with a function in the AKM programme. Read the next section, "Documentation".

Documentation

Documentation of the settings of the individual controllers can be made with the print function in the AKM programme. Select the controller for which documentation of the settings is required and select the "Print Settings" function (cf. also the AKM Manual).



Functions

Shown below are function groups with corresponding measurements and settings. A printout of the given settings can be made using the AKM function "Print Settings" (see above).

Note

It has been necessary to make selections among the many measurements and settings coming from the controller.

The operation from the AKM programme cannot contain them all.

If there is a need for access to all measurements and settings, you should make use of Service Tool type AK-ST 500.



Main settings

Measurements AK error When "ON", the controller is in alarm condition.

Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4)
Comp. ctrl. ref. °C Actual reference temp. for compressor capacity

(incl. external reference signal, if any)

Compressor capacity in % (of total capacity)

Request Compr. Cap % Reference for compressor capacity (deviations may be due to time delays)

P0 °C Suction pressure in °C. (Measured with the pressure transmitter) Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7)
Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Pc Bar Condensing pressure (measured with the pressure transmitter)
Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc Bar Actual gas cooler pressure

Pgc reference bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Sgc °C Actual temperature at outlet from the gas cooler

External Main Switch Status of input "Extern Main Switch". In pos. "OFF" the regulation is stopped by force

Settings Main switch Main switch: ON: Regulation

OFF: Controller stopped

Configuration lock Lock of configuration.

In order to select quick setup or select refrigerant type, the configuration lock must be "open". Note: "Main switch" must be OFF in order to set configuration lock in "open"

position 0: Open 1: Locked

Refrigerant type Po Select refrigerant type

0= not selected, 1=R12. 2=R22. 3=R134a. 4=R502. 5=R717. 6=R13. 7=R13b1. 8=R23. 9=R500. 10=R503. 11=R114. 12=R142b. 13=User defined 14=R32. 15=R227. 16=R401A. 17=R507. 18=R402A. 19=R404A. 20=R407C. 21=R407A. 22=R407B. 23=R410A. 24=R170. 25=R290. 26=R600. 27=R600a. 28=R744. 29=R1270. 30=R417A. 31=R422A. 32=R413A. 33=R422D. 34=R427A. 35=R438A. 36=XP10. 37=R407F.

Suction capacity control

Measurements AK error When "ON", the controller is in alarm condition.

Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4)

Comp. ctrl. ref. °C Actual reference temp. for compressor capacity

(incl. external reference signal, if any)

Compressor cap. % Cut-in compressor capacity in % (of total capacity)

Request Compr. Cap % Reference for compressor capacity (deviations may be due to time delays) P0 °C Suction pressure in °C. (Measured with the pressure transmitter)

Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7)
Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Pc Bar Condensing pressure (measured with the pressure transmitter)
Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc Bar Actual gas cooler pressure

Pgc reference Bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Sgc °C Actual temperature at outlet from the gas cooler

MC dP0 offset K Actual displacement value for the suction pressure in connection with a "P0

Optimiser" function (Master control function in AKA gateway)



S4 media temp. °C Actual media temperature measured at S4 sensor

(Only used if S4 is selected as control sensor)

Pctrl °C Actual regulation pressure measured with Pctrl pressure transmitter (cascade

pressure)

Suction status 0: Power up Controller has been powered up (power supply re-connected)

> 1: Stopped Capacity control has been stopped ("Main switch" = OFF or

> > "Control mode" = OFF)

2: Manual Capacity is controlled manually ("Control mode" = MAN) Capacity control is in alarm condition (fx. alarm on Po Min 3: Alarm

or Pc Max)

Capacity control is waiting for elapse of "Restart time" 4: Restart

5: Standby Capacity control is ready to start

6: State off timer 7-10: State on timer 11: Unloaded 12-14: Unload cutin

15: Full loaded All capacity cutin

16: Running Capacity control is running

Actual Zone Actual zone for capacity regulation:

> 0: P0-error 1: - - Zone 2: - Zone 3: NZ 4: + Zone 5: + + Zone Actual superheat

Suction superheat K

Night Setback Status of night setback function

ON: Night (An increase of the evaporating pressure is permitted)

OFF: Normal situation

Load shed 1 Actual status on Load shed input 1 Load shed 2 Actual status on Load shed input 2

Injection ON Status of the "Injection ON" function (earlier mentioned "AKC ON")

> 0: Forced closing of all AKV valves 1: Normal operation of AKC controllers

MT release output Actual status on "Comp. release" output signal from MT controller MT request input Actual status on "Comp. request" input signal on MT controller LT request output Actual status on "Comp. request" output signal from LT controller LT release input Actual status on "Comp. release" input signal on LT controller

No. of compressors Defined number of compressors

Comp. application Select the compressor application required (see the manual for further details)

0: Single step only

1: 1xComp. w. unloaders + Single step 2: 2xComp. w. unloaders + Single step 3: Comp. w. unloaders only

4: 1xVariable speed + Single step 5: 1xVariable speed + Comp. w. unloaders 6: 2xVariable speed + Single step

Step control mode Selected coupling pattern for compressors

Sequential: Compressors are cut in/out in strict accordance

with compressor number

Cyclic: Runtime equalisation between compressors Best fit: Compressors are cut in/out in order to make the best possible fit to actual load

0: Sequential 2: Cyclic 3: Best fit

Settings Main switch Main switch: ON: Regulation

Reference mode

OFF: Controller stopped

Cap. control mode 0: MAN (The compressor capacity will be controlled manually)

1: OFF (The capacity control will be stopped)

2: AUTO (The capacity is controlled by the PI controller)

Manual capacity % Manual setting of compressor capacity

> The value is in % of total capacity controlled by the controller Displacement of suction pressure as a function of external signals

0: Reference = set reference + night offset + offset from external 0-10 V signal 1: Reference = set reference + offset from P0 optimization + night offset



Setpoint °C Setting of required suction pressure in °C Min.Reference °C Min. permissible suction pressure reference Max.Reference °C Max. permissible suction pressure reference

Night offset K Displacement value for suction pressure in connection with an active night

setback signal (set in Kelvin)

++Zone delay s Time delay between step cut-ins in the regulation band over the "+Zone band"

Set in seconds

+Zone delay s Time delay between step cut-ins in the regulation band over the neutral zone

Set in seconds

+Zone band K Regulation band over the neutral zone
Neutral zone K Neutral zone for suction pressure
-Zone band K Regulation band under the neutral zone

-Zone delay s Time delay between step cut-outs in the regulation band under the neutral zone

Set in seconds

--Zone delay s Time delay between step cut-outs in the regulation band under the "-Zone band"

Set in seconds.

Kp Po Ampliflication factor for P0 regulation

VSD Min. speed Hz Minimum allowed speed before stop of Variable Speed drive (Low load condition)

VSD Start speed Hz Minimum speed for start of Variable speed drive (Must be set higher than

"VSD Min. Speed Hz")

VSD Max. speed Hz Highest permissible speed for the compressor motor

Sd max. limit °C Alarm at too high Sd Sd comp. alarm delay Time delay for Sd alarm P0 min. limit °C Alarm at too low P0 P0 max. alarm °C Alarm at too high P0 P0 max. delay m Time delay for P0 alarm SH min. alarm K Alarm at too low superheat SH max. alarm K Alarm at too high superheat SH alarm delay m Time delay for SH alarm

Load shed limit 1 Set max capacity limit for load shed input 1 Load shed limit 2 Set max capacity limit for load shed input 2

MT release delay s

Time delay on output signal "Comp. release" on MT controller

Time delay on input signal for "Comp. request" on MT controller

Time delay on output signal "Comp. request" on LT controller

Time delay on output signal "Comp. release" on LT controller

Time delay on input signal for "Comp. release" on LT controller

Select if a pump down function on the last compressor is requested

Po pump down limit °C Set the actual pump down limit for the last compressor

Initial start time The time after start-up where the cut-in capacity is limited to the first compressor step.

Safety restart time Time delay before restart of compressors

Suction compressor status

Measurements AK error When "ON", the controller is in alarm condition.

Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4)
Comp. ctrl. ref. °C Actual reference temp. for compressor capacity

(incl. external reference signal, if any)

Compressor cap. % Cut-in compressor capacity in % (of total capacity)

Request Comp. Cap % Reference for compressor capacity (deviations may be due to time delays)

P0 °C Suction pressure in °C. (Measured with the pressure transmitter)

Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7)
Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Pc Bar Condensing pressure (measured with the pressure transmitter)
Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc Bar Actual gas cooler pressure



Pgc reference Bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Sgc °C Actual temperature at outlet from the gas cooler

VSD 1 safety Status on safety input for variable speed controller on compressor 1

ON: Alarm OFF: No alarm

VSD 2 safety Status on safety input for variable speed controller on compressor 2

ON: Alarm OFF: No alarm

 ${\it VSD Speed \%} \\ {\it The present speed of the compressor motor controlled by the frequency converter} \\$

Comp. 1 Status 0: Power up Controller has been powered up/Compressor is not used

1: Stopped Compressor hat been stopped

2: Manual Compressor capacity is controlled manually
 3: Alarm Compressor is in alarm condition (cut out on safety)
 4: Restart Compressor is waiting for elapse of "Recycle time"

5: Standby Compressor is ready to start

6-10: Status_RUN_Timer

11: unloaded 12-14: Unloads cutin

15: Full loaded All capacity cutin

16: Running Capacity control is running

Comp 2 ... Status As above for compressor no. 2 to 8

Comp 1 capacity % Actual cut-in capacity on this compressor Comp 2 ...capacity % As above for compressor no. 2 to 8

Comp 1 Cycles / 24 h Number of compressor starts during the past 24 hours

Comp 2 ... Cycles / 24 h As above for compressor no. 2 to 8

Settings Main switch Main switch: ON: Regulation

OFF: Controller stopped

1 Min. ON-time m
2 ...Min. ON-time m
3 Min. OFF-time m
4 Min. OFF-time m
3 As above for compressor no. 2 to 8
4 Min. OFF-time m
5 As above for compressor no. 2 to 8
6 As above for compressor no. 2 to 8

1 Recycle time m Minimum period of time between two successive starts.

2 ...Recycle time m
 1 runtime h
 2 ...runtime h
 As above for compressor no. 2 to 8
 Compressor's total run time in hours
 As above for compressor no. 2 to 8

High pressure control

Measurements AK error When "ON", the controller is in alarm condition.

Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4)
Comp. ctrl. ref. °C Actual reference temp. for compressor capacity

(incl. external reference signal, if any)

Compressor cap. % Cut-in compressor capacity in % (of total capacity)

Request Comp. Cap % Reference for compressor capacity (deviations may be due to time delays)

P0 °C Suction pressure in °C. (Measured with the pressure transmitter)

Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7)
Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Pc Bar Condensing pressure (measured with the pressure transmitter)
Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc Bar Actual gas cooler pressure

Pgc reference Bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Sgc °CActual temperature at outlet from the gas coolerShp °CRead temperature at high pressure valveVhp OD%Read opening degree of high pressure valve



Rec. Status 0: Off

1: Standby 2: Normal

3: Emergency operation

4: Manual

Prec Bar Read pressure of receiver

Vrec OD% Read opening degree of receiver valve

Settings Main switch Main switch: Regulation ON:

> Controller stopped OFF:

HP control ManAut Control of high pressure valve: 1=automatic, 2=manual override Vhp manual OD% Manual setting of opening degree of high pressure valve

Pgc min. Bar Setting of gas coolers min. pressure Pgc max. Bar Setting of gas coolers max. pressure

Extra capacity offs Set requested pressure increase if the "extra cooling capacity" is activated

dT Subcool K Set requested sub cooling in the sub critical range

Rec. Control ManAut Control of receiver valve: 1=automatic, 2=manual override Rec. Manual OD% Manual setting of opening degree of the receiver valve

Prec setpoint Bar Set requested receiver pressure

Oil management

Measurements AK error When "ON", the controller is in alarm condition.

Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4) Comp. ctrl. ref. °C Actual reference temp. for compressor capacity

(incl. external reference signal, if any)

Compressor cap. % Cut-in compressor capacity in % (of total capacity)

Request Comp. Cap % Reference for compressor capacity (deviations may be due to time delays) Suction pressure in °C. (Measured with the pressure transmitter)

P0 °C Ss Suction gas °C

Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7) Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Condensing pressure (measured with the pressure transmitter) Pc Bar Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc Bar Actual gas cooler pressure

Pgc reference Bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Sqc °C Actual temperature at outlet from the gas cooler

Rec. pressure Actual pressure in receiver Rec. pres. buildup Status of oil separator

Settings Main switch Main switch: ON: Regulation

OFF: Controller stopped

Interval time Time between breaks. (Simple oil equalisation) Duration of oil equalisation (Simple oil equalisation) Equalisation time Rec. pres. cutin Bar Reciever pressure, which to cutin for the oil Rec.pres.cutout Bar Receiver pressure, which to cutout for the oil

High alarm limit Bar Alarm limit high Low alarm limit Bar Alarm limit low

High alarm delay m Delay time for high pressure alarm Low alarm delay m Delay time for low pressure alarm Lvl. alarm delay s Delay time for Level alarm

Condenser capacity control

Measurements AK error

When "ON", the controller is in alarm condition. Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4) Comp. ctrl. ref. °C Actual reference temp. for compressor capacity

(incl. external reference signal, if any)



Compressor cap. % Cut-in compressor capacity in % (of total capacity)

Request Comp. Cap % Reference for compressor capacity (deviations may be due to time delays)

P0 °C Suction pressure in °C. (Measured with the pressure transmitter)
Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7)
Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Pc Bar Condensing pressure (measured with the pressure transmitter)
Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc Bar Actual gas cooler pressure

Pgc reference Bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Sgc °C Actual temperature at outlet from the gas cooler
Tc max. limit °C Readout limit value for max condenser pressure
S7 brine temp °C Actual media temperature measured at S7 sensor
(Only used if S7 is selected as control sensor)

Condenser status 0: Power up Controller has been powered up (power supply re-connected)

1: Stopped Capacity control has been stopped ("Main switch" = OFF or

"Control mode" = OFF)

Manual Capacity is controlled manually ("Control mode" = MAN)
 Alarm Capacity control is in alarm condition (f.ex. Pc Max or Sd Max)
 Restart Capacity control is waiting for elapse of "Restart time"

5: Standby Capacity control is ready to start

6: Unloaded 7-9 Part loaded

10: Full loaded All capacity cutin11: Running Capacity control is running

Air flow status 0: No RFG. selectNo refrigerant has been selected (monitoring of air

flow can not start)

1: Tuning Monitoring function adapts to the condenser in question

2: OFF Monitoring function is switched OFF

3: OK Air flow is OK

4: Little dirt The amount of dirt decreases the performance of the condenser,

clean when possible

5: Dirty The amount of dirt leads to considerable air flow problems, clean

as soon as possible

6: Blocking The amount of dirt might lead to high pressure problems, clean

now

Sc3 Air on °C Outdoor temperature in °C measured with Sc3 temperature sensor

No. of fans Defined number of fans

VSD Speed % Status of analogue output signal "AO" for variable speed drive (in percent of

full scale f.ex. 0 -10 V d.c.)

VSD safety Status of safety monitoring input for Variable Speed Drive

ON: Alarm on VSD A safety monitoring input OFF: No alarm on VSD A safety monitoring input

Settings Main switch Main switch: ON: Regulation

OFF: Controller stopped

Condenser ctrl mode 0: MAN (The condenser capacity will be controlled manually)

1: OFF (The capacity control will be stopped)

2: AUTO (The capacity is controlled by the PI controller)

Manual capacity % Manual setting of condenser capacity

The value is in % of total capacity controlled by the controller

Pc Ref. mode 0: Set point Reference = "PcA setpoint °C"

1: Floating Reference is changed as a function of the outdoor temperature

measured by the "Sc3 air on" sensor, the set "Dimensioning tm K"

and the actual compressor load.

Cond. Setpoint °C Setting of required discharge pressure in °C

Dimensioning tm K Dimensioning mean temperature differential between air- and condensing temperature at full load for the condenser in question (Typical 8 – 15K).



Min. tm k tm value at minimum load.

Min. Reference °C Min. permissible condensing pressure reference Max. Reference °C Max. permissible condensing pressure reference Capacity Lim. night % Capacity limitation during night operation

Kp Amplification factor P/PI controller
Tn s Integration time for PI controller

VSD Min. speed % Minimum allowed speed before stop of Variable Speed drive (Low load condition)

VSD Start speed % Minimum speed for start of Variable speed drive (Must be set higher than

"VSD Min. Speed %")

Pc max limit Bar Max. limit for condensing pressure Pc max alarm delay m Time delay for "Pc max alarm"

Condenser fan status

Measurements AK error When "ON", the controller is in alarm condition. Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4)

Comp. ctrl. ref. °C Actual reference temp. for compressor capacity (incl. external reference signal, if any)

Compressor cap. % Cut-in compressor capacity in % (of total capacity)

Request Compr. Cap % Reference for compressor capacity (deviations may be due to time delays)

P0 °C Suction pressure in °C. (Measured with the pressure transmitter)

Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7) Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Pc Bar Condensing pressure (measured with the pressure transmitter)
Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc bar Actual gas cooler pressure

Pgc reference bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Sgc °C Actual temperature at outlet from the gas cooler

Fan 1/VSD status Status of the Fan 1
ON: Fan is running
OFF: Fan is not running

As above for fan 2 to 8

Settings Main switch Main switch: ON: Regulation

Fan2.... status

OFF: Controller stopped

Heat recovery

Measurements AK error When "ON", the controller is in alarm condition.

Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4)

Comp. ctrl. ref. °C Actual reference temp. for compressor capacity

(incl. external reference signal, if any)
Compressor cap. %
Cut-in compressor capacity in % (of total capacity)

Reguest Compr. Cap % Reference for compressor capacity (deviations may be due to time delays)

P0 °C Suction pressure in °C. (Measured with the pressure transmitter)

Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7) Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Pc Bar Condensing pressure (measured with the pressure transmitter)
Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.



Pgc Bar Actual gas cooler pressure

Pgc reference Bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Sqc °C Actual temperature at outlet from the gas cooler Shr2 °C (ONLY at CO2). Temperature at sensor Shr2 Stw2 °C (ONLY at CO2). Temperature at sensor Stw2

Status heat circuit (ONLY at CO2). 0=off. 1=waiting. 2=started. 3=standard. 4=variable offset

5=max recovery. 6=stopped. 7=error.

Tw Stw8 °C (ONLY at CO2). Temperature at sensor Stw8. Tap water

Tw Status (ONLY at CO2). 0=off. 1=waiting. 2=started. 3=hot tap water. 5=manual.

6= stopped. 7=error. 8=Flow error. 9=sensor error. 10=boiling.

(ONLY at CO2). Readout about tap water circuit can be activated automatically Tw enable

Hr Shr8 °C (ONLY at CO2). Temperature at sensor Shr8. Heat circuit

Hr Status (ONLY at CO2). 0=off. 1=waiting. 2=started. 3=heat circuit. 5=manual.

6= stopped. 7=error. 8=Flow error. 9=sensor error. 10=boiling.

Hr enable (ONLY at CO2). Readout about heat circuit can be activated automatically HR thermostat temp°C (Not at CO2). Actual temperature at sensor for heat recovery function

Heat recovery status (Not at CO2). Status on heat recovery function (on/off)

Settings Main switch Main switch: Regulation

> OFF: Controller stopped (ONLY at CO2). Set point for tap water temperature

Tw setpoint °C Hr setpoint °C (ONLY at CO2). Set point for heat circuit temperature Pgc HR max. offset (ONLY at CO2). Displacement pressure of max. signal

Pgc HR min. Bar (ONLY at CO2). Set point at min. signal

Heat recovery SP °C (Not at CO2). Reference for condenser pressure when heat recovery is on HR temp. cutin °C (Not at CO2). Temperature value when thermostat switch to heat recovery HR temp. cutout °C (Not at CO2). Temperature value when thermostat switch off the heat recovery

Alarm priorities

Measurements When "ON", the controller is in alarm condition. AK error

> Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4) Comp. ctrl. ref. °C Actual reference temp, for compressor capacity

> > (incl. external reference signal, if any)

Compressor cap. % Cut-in compressor capacity in % (of total capacity)

Request Comp. Cap % Reference for compressor capacity (deviations may be due to time delays)

P0°C Suction pressure in °C. (Measured with the pressure transmitter)

Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7) Cond. ctrl. ref. °C Actual reference temp, for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Pc Bar Condensing pressure (measured with the pressure transmitter) Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Actual gas cooler operation: Gc status

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc Bar Actual gas cooler pressure

Pgc reference Bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Sqc °C Actual temperature at outlet from the gas cooler

Main switch Settings Main switch: ON: Regulation

> Controller stopped OFF:

The alarm priority of the following alarms can be changed:

High priority is defined with setting = 1Medium priority is defined with setting = 2 Low priority is defined with setting = 3

Log only = 4

Overriding the alarms is defined with setting = 0

Main Switch 0/1/2/3/4 Low P0 0/1/2/3/4



High P0 High Pc/Sd Hpcontrol / Receive Superheat Min/Max Load shedding P0/S4/Pctrl error Misc. sensors Comp. common safety Comp. VSD safety Comp. 2 safety Comp. 3 safety Comp. 4 safety Comp. 5 safety Comp. 6 safety Comp. 7 safety Comp. 7 safety Comp. 8 safety Comp. 8 safety Comp. 8 low Fan safety Comp. High Oil Ivl Oil Separator alarm Oil Receiver alarm Oil Receiver alarm Oil Recv. Low press	0/1/2/3/4 0/1/2/3/4
on necesses alarm	
5 .	
Tw boiling alarm	0/1/2/3/4
Hr boiling alarm	0/1/2/3/4
3	

General alarm inputs

Measurements	AK error	When "ON", the controller is in alarm condition.
	Comp. ctrl. temp °C	Actual temperature for control sensor (Po or S4)

Comp. ctrl. ref. °C Actual reference temp. for compressor capacity

(incl. external reference signal, if any)
Compressor cap. %
Cut-in compressor capacity in % (of total capacity)

Request Compr. Cap % Reference for compressor capacity (deviations may be due to time delays)

P0 °C Suction pressure in °C. (Measured with the pressure transmitter)

Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7) Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Pc Bar Condensing pressure (measured with the pressure transmitter)
Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc Bar Actual gas cooler pressure

Pgc reference Bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

ON: Alarm is activ

OFF: No alarm, normal situation

DI 2.... Input As above, but for the alarm functions 2 to 6

Main switch Main switch: ON: Regulation

OFF: Controller stopped

DI 1 Alarm delay m
DI 2... Alarm delay m
Time delay for the alarm "DI 1 Alarm"
As above, but for the alarm functions 2 to 6

Settings



Thermostat/pressostats

When "ON", the controller is in alarm condition. Measurements AK error Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4)

Comp. ctrl. ref. °C Actual reference temp. for compressor capacity

(incl. external reference signal, if any)

Compressor cap. % Cut-in compressor capacity in % (of total capacity)

Request Comp. Cap % Reference for compressor capacity (deviations may be due to time delays)

P0 °C Suction pressure in °C. (Measured with the pressure transmitter)

Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7) Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

(incl. external contributions, if any)

Cond. cap. % Cut-in condenser capacity in % (of total capacity)

Request Cond. cap % Reference for condenser capacity

Pc Bar Condensing pressure (measured with the pressure transmitter) Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc Bar Actual gas cooler pressure

Pgc reference Bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Actual temperature at outlet from the gas cooler Sgc °C

Thermostat 1 °C Temperature measurement of function defined in Thermostat 1. Thermostat 2 °C Temperature measurement of function defined in Thermostat 2. Thermostat 3 °C Temperature measurement of function defined in Thermostat 3. Pressostat 1 Bar Pressure measurement of function defined in Pressostat 1

Pressostat 2 Bar As above but for Pressostat 2 Pressostat 3 Bar As above but for Pressostat 3

Settings Main switch Main switch: ON: Regulation

OFF: Controller stopped

Cutin value for function defined in "Thermostat 1". T1 Cutin °C T1 Cutout °C Cutout value for function defined in "Thermostat 1".

T1 High Alarm °C High alarm limit "Thermostat 1" T1 Low Alarm °C Low alarm limit "Thermostat 1"

T1 High Al delay m Time delay for high alarm "Thermostat 1" T1 Low Al delay m Time delay for low alarm "Thermostat 1"

P1 Cutin press Bar Cutin value for function defined in "Pressostat 1". P1 Cutout press Bar Cutout value for function defined in "Pressostat 1".

P1 High Al limit Bar High alarm limit "Pressostat 1" P1 Low Al limit Bar Low alarm limit "Pressostat 1"

Time delay for high alarm "Pressostat 1" P1 High Al delay m P1 Low Al delay m Time delay for low alarm "Pressostat 1"

(Use Service Tool if data concerning thermostats 2 to 5 or from Pressostat 2 to 5 have to be downloaded).

Voltage and PI inputs

Measurements AK error When "ON", the controller is in alarm condition.

Comp. ctrl. temp °C Actual temperature for control sensor (Po or S4) Comp. ctrl. ref. °C Actual reference temp. for compressor capacity

(incl. external reference signal, if any)

Compressor cap. % Cut-in compressor capacity in % (of total capacity) Request Comp. Cap % Reference for compressor capacity (deviations may be due to time delays)

P0°C Suction pressure in °C. (Measured with the pressure transmitter)

Ss Suction gas °C Actual suction gas temperature

Cond. ctrl. temp °C Actual temperature for control sensor (Pc or S7) Cond. ctrl. ref. °C Actual reference temp. for condenser capacity

> (incl. external contributions, if any) Cut-in condenser capacity in % (of total capacity)

Cond. cap. %

Reference for condenser capacity Request Cond. cap %



Pc bar Condensing pressure (measured with the pressure transmitter)
Tc °C Condensing pressure in °C. (measured with the pressure transmitter)

Gc status Actual gas cooler operation:

0=Off. 1=Standby. 2=Max COP operation. 3=Heat recovery. 4=Extra capacity.

5=Manual control.

Pgc Bar Actual gas cooler pressure

Pgc reference Bar Actual reference for gas cooler pressure Sd discharge gas °C Actual discharge gas temperature

Sgc °C Actual temperature at outlet from the gas cooler
V1 Actual input Voltage measurement on the function defined in Volt 1.
V2 Actual input Voltage measurement on the function defined in Volt 2.
V3 Actual input Voltage measurement on the function defined in Volt 3.

PI1 State PI function state

PI1 Alarm state PI function alarm condition

PI1 Input Input signal
PI1 Reference Reference
PI1 Output value Output value

PI1 Output type Output type: PWM. Stepper. Voltage

Settings Main switch Main switch: ON: Regulation

OFF: Controller stopped

V1 Cutin The value where the relay is to cut in V1 Cutout The value where the relay is to cut out

V1 Cutin delay m
V1 Cutout delay m
V1 High Al Limit
V1 Low Al Limit
V1 High Al delay m
V1 High Al delay m
V1 Low Al delay m
Time delay for cutin of relay
Time delay for the high alarm limit
The value for the low alarm
Time delay for high alarm
Time delay for low alarm

PI1 Off Aut Man
Control of PI function. 0: Off, 1: Automatic, 2: Manual
PI1 Manual OD
Manual setting of opening degree for PI function

(Use Service Tool if data concerning Volt 2, 3, 4, 5 and PI2 /PI3 are to be downloaded).

AKM menu: "For DANFOSS only"

This menu contains data and setting values for special internal controller functions. **Do not change the stated values.**