

Turnkey Electrical and Automation System Implementation for Gold Mining Operations: A Case Study of Söğüt Gold Mine Plant

Pacpro Engineering Solutions

www.pacpro.com

Corresponding Author: info@pacpro.com

Abstract



This paper presents a comprehensive case study of the turnkey electrical and automation system implementation at the Söğüt Gold Mine Plant operated by Gübretaş Maden Yatırımları in Bilecik, Turkey. The project involved the design, procurement, and commissioning of a complete electrical and automation infrastructure within an aggressive 11-month timeline. The solution incorporated advanced technologies including Siemens PCS7 distributed control system (DCS), intelligent motor control centers (MCCs), medium voltage (MV) distribution systems, and prefabricated eHouse solutions. This study demonstrates how integrated turnkey approaches can successfully address the challenges of modern mining operations while ensuring reliability, scalability, and operational efficiency. The implementation resulted in a fully automated gold processing facility capable of both open-pit and underground mining operations, with provisions for future capacity expansion and digital technology integration.

1. Introduction

The mining industry faces increasing pressure to improve operational efficiency, safety, and environmental compliance while managing complex technical challenges. Modern gold

mining operations require sophisticated electrical and automation systems to optimize extraction processes, ensure worker safety, and maintain consistent production quality. This paper examines the successful implementation of a comprehensive turnkey electrical and automation solution at the Söğüt Gold Mine Plant in Turkey.

The Söğüt Gold Mine, located in the Bilecik province, represents a significant investment in Turkey's mining sector. The facility operates both open-pit and underground mining methods, requiring a flexible and robust automation infrastructure. The project presented unique challenges including an aggressive timeline, global supply chain disruptions due to COVID-19, and the need for a scalable system architecture capable of future expansion.

This case study provides insights into the design methodology, implementation strategies, and technological solutions employed to deliver a state-of-the-art mining automation system within the specified constraints.

2. Literature Review and Background

Modern mining operations increasingly rely on integrated automation systems to achieve operational excellence. The evolution from traditional manual operations to fully automated systems has been driven by several factors including safety requirements, operational efficiency, and economic pressures.

Distributed Control Systems (DCS) have become the backbone of modern process industries, including mining operations. The integration of field devices, control systems, and enterprise software platforms enables comprehensive monitoring and control of complex processes. Recent developments in industrial communication protocols, particularly PROFINET and PROFIBUS, have enhanced the reliability and performance of these systems.

The concept of prefabricated electrical houses (eHouses) has gained significant traction in industrial projects due to their ability to reduce installation time, improve quality control, and minimize on-site construction risks. These solutions are particularly valuable in remote mining locations where traditional construction methods face logistical challenges.

3. Project Methodology and Approach

3.1 Project Scope and Requirements

The Söğüt Gold Mine project encompassed the complete electrical and automation infrastructure for a greenfield mining operation. The scope included:

- Medium Voltage (MV) transformers and switchgear systems
- Low Voltage (LV) distribution and motor control centers
- Distributed Control System (DCS) based on Siemens PCS7

- Variable Frequency Drives (VFDs) and soft starters
- Uninterruptible Power Supply (UPS) systems
- Industrial communication networks
- Prefabricated eHouse solutions for equipment housing

The client's primary requirements focused on system reliability, scalability for future expansion, and integration capabilities with third-party enterprise software platforms.

3.2 Design Philosophy and Architecture

The system architecture was designed around a hierarchical control structure with the Siemens PCS7 DCS serving as the central control platform. Key design principles included:

- Redundancy at critical control levels to ensure high availability
- Open architecture for future technology integration
- Standardized process libraries for consistent operation
- Modular design approach for scalability
- Integration of safety systems with process control

The electrical distribution system was designed to IEC standards with appropriate protection and coordination schemes to ensure safe and reliable operation.

4. System Implementation



4.1 eHouse / SubStation Solution Benefits

The implementation utilized prefabricated eHouse solutions to address project timeline and quality requirements. Key advantages included:

- Pre-assembly and testing in controlled factory conditions
- Reduced on-site installation time through plug-and-play approach
- Integrated housing for multiple system components
- Enhanced protection against environmental conditions
- Reduced cable installation costs
- Improved commissioning efficiency



- Space optimization compared to traditional concrete structures

The eHouse approach proved particularly valuable given the project's aggressive timeline and the challenges posed by global supply chain disruptions during the COVID-19 pandemic.

4.2 Control System Architecture



The control system implementation featured:

- Redundant PCS7 controllers for high availability
- ET200 HA I/O modules for critical process points
- Redundant PROFINET network infrastructure
- SCALANCE managed switches for network reliability
- Integration with intelligent MCC units

featuring Simocode protection

- Web-based monitoring and reporting capabilities

The system architecture supports both local and remote operation modes, enabling flexible operational strategies and remote monitoring capabilities.

5. Results and Performance Analysis

5.1 Project Delivery Performance



The project was successfully completed within the specified 11-month timeline despite global supply chain challenges. Key performance indicators included:

- On-time delivery of all major system components
- Successful factory acceptance testing of eHouse / SubStation modules
- Efficient site installation and commissioning
- Achievement of production targets during startup phase
- Zero safety incidents during installation and commissioning

The turnkey approach enabled effective project management and coordination across multiple technical disciplines.

5.2 Operational Benefits

The implemented system has delivered significant operational benefits:

- Enhanced process visibility and control through integrated DCS
- Improved equipment reliability through intelligent protection systems
- Reduced maintenance requirements through predictive monitoring
- Flexible production capabilities supporting both mining methods
- Scalable architecture supporting future capacity expansion
- Integration readiness for enterprise software and laboratory systems

The system's open architecture has proven valuable for ongoing optimization and future technology integration initiatives.

6. Challenges and Solutions

Several significant challenges were encountered and successfully addressed during the project:

****Supply Chain Disruptions****: Global supply chain issues due to COVID-19 were mitigated through alternative sourcing strategies and backup supplier networks.

****Timeline Constraints****: The aggressive 11-month schedule was met through the eHouse prefabrication approach and parallel engineering activities.

****System Integration Complexity****: The integration of multiple technology platforms was achieved through standardized communication protocols and comprehensive testing procedures.

****Remote Location Logistics****: The mining site's remote location required careful planning of transportation and installation sequences.

****Future Scalability Requirements****: The system architecture was designed with modular expansion capabilities to accommodate future growth.

7. Conclusions and Future Work

This case study demonstrates the successful implementation of a comprehensive turnkey electrical and automation solution for modern gold mining operations. The project achieved its primary objectives of delivering a reliable, scalable, and technologically advanced system within challenging timeline constraints.

Key success factors included:

- Integrated turnkey project approach
- Utilization of prefabricated eHouse solutions
- Robust system architecture with redundancy
- Effective project management and risk mitigation
- Strong supplier partnerships and alternative sourcing strategies

The implemented system provides a solid foundation for current operations while maintaining flexibility for future technological advancement and capacity expansion. The success of this project validates the effectiveness of turnkey approaches in complex industrial automation implementations.

Future work will focus on the integration of advanced analytics, artificial intelligence, and IoT technologies to further enhance operational efficiency and predictive maintenance capabilities.

Appendix A: Technical Specifications

System Component	Specification
Control System	Siemens PCS7 with redundant controllers
I/O Modules	ET200 HA high availability modules
Communication	PROFINET/PROFIBUS with redundant networks
MCC Systems	Sivacon S8 Form 4b with Simocode protection
Network Infrastructure	SCALANCE managed industrial switches
Power Distribution	MV/LV switchgear with protection coordination
Drive Systems	Variable frequency drives and soft starters
Housing Solution	Prefabricated eHouse modules
UPS Systems	Redundant uninterruptible power supplies
HMI/SCADA	PCS7 operator stations with web access