Job Name/Location:		iag No.:
Date:	For:☐ File ☐ Resubn	nit
PO No.:	☐ Approval ☐ Other_	
Architect:	GC:	-
Engr:	Mech:	
Rep:	(Project Manager)	

## KNUJB241A

Multi FR32 Convertible Mid Static Ducted

## Performance:

	Nominal Cooling Capacity (Btu/h)	24,000
1	Nominal Heating Capacity (Btu/h)	27,000

Cooling Nominal Test Conditions: Indoor: 80°F DB / 67°F WB Outdoor: 95°F DB / 75°F WB

Heating Nominal Test Conditions: Indoor: 70°F DB / 60°F WB Outdoor: 47°F DB / 43°F WB

### **Electrical:**

Power Supply (V/Hz/Ø) <sup>1,2</sup>	208-230/60/1
Rated Amps (A)	1.7

## Piping:

Installed Liquid Pipe (in., O.D.)	ø1/4
Installed Vapor Pipe (in., O.D.)	ø1/2
Liquid Connection (in., O.D.)	ø3/8
Vapor Connection (in., O.D.)	ø5/8
Drain (in., O.D. / I.D.)	1-1/4 / 1
Temperature Sensor	Thermistor

· Auto restart

• Sleep mode • Timer (on/off/weekly)

Drain pump

• ESP control

• R32 leak detection sensor

## **Controls Features:**

- Inverter (variable speed fan)
- · Long-life washable prefilter
- Hot start
- Self diagnosis
- Soft dry operation
- Auto operation
- Horizontal or vertical installation
- · Horizontal rear or horizontal bottom return

## **Optional Accessories:**

- ☐ Single-Port Shutoff Valve PRHPZ010A
- ☐ Auxiliary Heater Kit PRARH1
- ☐ Filter box ZFBXM A01A
- $\hfill\Box$  Vertical installation kit ABDAM A0

## **Controller Options:**

- □ MultiSITE™ CRC\* Controllers
- ☐ Simple Remote Controllers
- ☐ Standard III Remote Controllers
- □ Deluxe Remote Controller
- ☐ Remote Temperature Button Sensor
- □ Dry Contacts
- □ Wi-Fi Module PWFMDD200





## **Entering Mixed Air:**

Cooling (°F WB)	57 ~ 77
Heating (°F DB)	59 ~ 81

### **Unit Data:**

Refrigerant Type	R32
Refrigerant Control	EEV
Sound Pressure (H/M/L) dB(A) <sup>3</sup>	38 / 33 / 30
Primary Filter	Washable Pre-filter
Net Weight (lbs.)	64.2
Shipping Weight (lbs.)	74.3

#### Fan:

Туре	Sirocco
Quantity	1
Motor/Drive	Brushless Digitally Controlled/Direct
Air Flow H/M/L (CFM)	706.3 / 547.4 / 459.1
External Static Pressure <sup>4,5</sup> (in wg)	0.24
Minimum External Static Pressure	0.1
Maximum External Static Pressure	0.59
Dehumidification (pts./hr.)	4.23

## Notes:

- 1. Acceptable operating voltage: 187V-253V.
- 2. The power wiring and the communication wiring from the outdoor unit to the indoor unit, or from the branch distribution unit to the indoor unit is field supplied and must be stranded, shielded or unshielded (if shielded, it must be grounded to the chassis of the outdoor unit only). All wiring must comply with applicable local and national codes.
- a. Power wiring and communication wiring from outdoor unit to indoor unit (No. x AWG) 3 x 14 / 2 x 18. b. Power wiring and communication wiring from branch distribution unit to indoor unit (No. x AWG) 3 x 14 / 2 x 18.
- 3. Sound Pressure levels are tested in an anechoic chamber under ISO Standard 3745.4. Adjust fan speed to correct for static pressure increases when using field-supplied air filter.
- At factory fan speed setting.
- 6. See Engineering Manual for sensible and latent capacities.7. The indoor unit comes with a dry helium charge.
- 8. Corresponding refrigerant piping length is in accordance with standard length of each outdoor unit and the level difference is 0 ft. All capacities are net with a combination ratio between 95 - 105%.
- 9. Must follow installation instructions in the applicable LG installation manual.





# KNUJB241A

## Multi F R32 Convertible Mid Static Ducted

24.000 Btu/h



