

SILICON LABS SDK 3.5.6.0 GA Proprietary Flex Development **Software User Guide**

Home » SILICON LABS » SILICON LABS SDK 3.5.6.0 GA Proprietary Flex Development Software User Guide 🖺



Contents

- 1 SILICON LABS SDK 3.5.6.0 GA Proprietary Flex Development **Software**
- **2 Product Usage Instructions**
- 3 Connect Applications
- **4 Connect Stack**
- **5 RAIL Applications**
- **6 RAIL Library**
- 7 Using This Release
- 8 Installation and Use
- 9 Documents / Resources
 - 9.1 References
- 10 Related Posts



SILICON LABS SDK 3.5.6.0 GA Proprietary Flex Development Software

SiliconLabs/ gecko_sdk



The Gecko SDK (GSDK) combines our Series 0 and Series 1 IoT product software development kits (SDKs) based on Gecko...

₽ 4 ○ 0 ☆ 343 ♀ 151 Contributors Issues Stars Forks



Specifications

Proprietary Flex SDK version: 3.5.6.0 GA

- Gecko SDK Suite version: 4.2, July 3, 2024
- SDK Features: RAIL and Connect options for wireless applications
- RAIL Features: Radio Abstraction Interface Layer for radio interface support
- Connect Features: IEEE 802.15.4-based networking stack for low power consumption
- Compatible Compilers: GCC version 10.3-2021.10

Product Usage Instructions

Installation

Ensure you have the correct SDK version and compatible compiler installed.

Choosing Implementation Options

The Flex SDK offers two implementation options: RAIL and Connect. Select the appropriate option based on your project requirements.

RAIL Implementation

Utilize Silicon Labs RAIL for customizable radio interface support for both proprietary and standards-based wireless protocols.

Connect Implementation

Utilize Silicon Labs Connect for IEEE 802.15.4-based networking stack suitable for low power consumption and sub-GHz or 2.4 GHz frequency bands.

Documentation and Sample Applications

The Flex SDK comes with extensive documentation and sample applications. Refer to the provided source code within the SDK for examples.

Frequently Asked Questions (FAQ)

- Q: Where can I find security updates and notices for the SDK?
 - A: For security updates, refer to the Security chapter of the Gecko Platform Release notes or visit https://www.silabs.com/developers/flex-sdk-connect-networking-stack
- Q: How can I subscribe to Security Advisories for up-to-date information?
 - A: Silicon Labs recommends subscribing to Security Advisories for the latest information. Instructions can be found in the documentation or by visiting the provided link.

Proprietary Flex SDK 3.5.6.0 GA Gecko SDK Suite 4.2 July 3, 2024

The Proprietary Flex SDK is a complete software development suite for proprietary wire-less applications. Per its namesake, Flex offers two implementation options.

The first uses Silicon Labs RAIL (Radio Abstraction Interface Layer), an intuitive and easily-customizable radio interface layer designed to support both proprietary and standards-based wireless protocols.

The second uses Silicon Labs Connect, an IEEE 802.15.4-based networking stack de-signed for customizable broad-based proprietary wireless networking solutions that re-quire low power consumption and operates in either the sub-GHz or 2.4 GHz frequency bands. The solution is targeted towards simple network topologies.

The Flex SDK is supplied with extensive documentation and sample applications. All examples are provided in source code within the Flex SDK sample applications.

These release notes cover SDK version

- 3.5.6.0 GA released July 3, 2024
- 3.5.5.0 GA released January 24, 2024
- 3.5.4.0 GA released August 16, 2023
- 3.5.3.0 GA released May 3, 2023
- 3.5.2.0 GA released March 8, 2023
- 3.5.1.0 GA released February 1, 2023
- 3.5.0.0 GA released December 14, 2022

Compatibility and Use Notices

For information about security updates and notices, see the Security chapter of the Gecko Platform Release notes installed with this SDK or on the TECH DOCS tab on https://www.silabs.com/developers/flex-sdk-connect-networking-stack Silicon Labs also strongly recommends that you subscribe to Security Advisories for up-to-date information. For instructions, or if you are new to the Silicon Labs Flex SDK, see Using This Release.

Compatible Compilers

IAR Embedded Workbench for ARM (IAR-EWARM) version 9.20.4

- Using wine to build with the larBuild.exe command line utility or IAR Embedded Workbench GUI on macOS or Linux could result in incorrect files being used due to collisions in wine's hashing algorithm for generating short file names.
- Customers on macOS or Linux are advised not to build with IAR outside of Simplicity Studio. Customers who
 do should carefully verify that the correct files are being used.

GCC (The GNU Compiler Collection) version 10.3-2021.10, provided with Simplicity Studio.

Proprietary



RAIL APPS AND LIBRARY KEY FEATURES

- FG25 Flex-RAIL GA support
- New Long Range PHYs support for 490 MHz and 915 MHz
- xG12 dynamic mode switching support in RAIL
- · xG22 extended band support

CONNECT APPS AND STACK KEY FEATURES xG24 Connect support

Connect Applications

New Items

Added in release 3.5.0.0 XG24 Support

Improvements

Changed in release 3.5.0.0 OQPSK Long Range PHYs for XFG23

Fixed Issues

None

Known Issues in the Current Release

Issues in bold were added since the previous release. If you have missed a release, recent release notes are available on the TECH DOCS tab on https://www.silabs.com/developers/flex-sdk-connect-networking-stack

ID#	Description	Workaround
652925	EFR32XG21 is not supported for "Flex (Connect) – SoC Light Example DMP" and "Flex (Connect) – So C Switch Example"	

Deprecated Items

None

Removed Items

None

Connect Stack

New Items

Added in release 3.5.0.0 XG24 Support

Improvements

None

Fixed Issues

None

Known Issues in the Current Release

Issues in bold were added since the previous release. If you have missed a release, recent release notes are available on the TECH DOCS tab on https://www.silabs.com/developers/gecko-software-development-kit

ID#	Description	Workaround
389462	When running the RAIL Multiprotocol Library (used for example when running DMP Connect+BLE), IR Calibration is not performed because of a known is sue in the RAIL Multiprotocol Library. As result, the re is an RX sensitivity loss in the order of 3 or 4 dB m.	
501561	In the Legacy HAL component, the PA configuration is hard-coded regardless of the user or board set tings.	Until this is changed to properly pull from the configuration header, the file ember-phy.c in the user's project will need to be modified by hand t o reflect the desired PA mode, voltage, and ra mp time.
711804	Connecting multiple devices simultaneously may fa il with a timeout error.	

Deprecated Items

None

Removed Items

None

RAIL Applications

New Items

Added in release 3.5.0.0

- XG25 Support
- RAIL SoC Mode Switch Application

Improvements

Changed in release 3.5.0.0

- RAIL SoC Long Preamble Duty Cycle support for XG24
- OQPSK Long Range PHYs for XFG23

Fixed Issues

Fixed in release 3.5.1.0

ID#	Description
	Mode Switch: MCS Rate selection fix for OFDM.

Known Issues in the Current Release

None

Deprecated Items

None

Removed Items

- RAIL SoC Long Preamble Duty Cycle (Legacy)
- RAIL SoC Light Standard
- · RAIL SoC Switch Standard

RAIL Library

New Items

Added in release 3.5.2.0

Added RAIL_PacketTimeStamp_t::packetDurationUs field, which is currently set only on EFR32xG25 for received OFDM packets.

Added in release 3.5.0.0

- Added HFXO temperature compensation in RAIL on platforms that support
 RAIL_SUPPORTS_HFXO_COMPENSATION. This feature can be configured with the new
 RAIL_ConfigHFXOCompensation() API. The user will also need to be sure to handle the new
 RAIL_EVENT_THERMISTOR_DONE event to trigger a call to RAIL_CalibrateHFXO to perform the
 compensation.
- Added options in "RAIL Utility, Protocol" component to control whether Z-Wave, 802.15.4 2.4 GHz and Sub-GHz, and Bluetooth LE are enabled so that the user can save space in their application by disabling unused protocols.
- Added a new API RAIL_ZWAVE_PerformIrcal to help perform an IR calibration across all the different PHYs
 used by a Z-Wave device.
- Added 40 MHz crystal support on EFR32xG24 devices to the "RAIL Utility, Built-in PHYs Across HFXO Frequencies" component.
- Added support for IEEE 802.15.4 fast RX channel switching with the new
 RAIL_IEEE802154_ConfigRxChannelSwitching API on supported platforms (see
 RAIL_IEEE802154_SupportsRxChannelSwitching). This feature allows us to simultaneously detect packets on
 any two 2.4 GHz 802.15.4 channels with a slight reduction in overall sensitivity of the PHY.
- Added a new Thermal Protection feature, on platforms that support
 RAIL_SUPPORTS_THERMAL_PROTECTION, to track temper-ature and prevent transmits when the chip is too hot.
- Added new table-based OFDM and FSK PAs for EFR32xG25 based devices. The output power of these can be
 modified through a new customer provided look-up table. Ask support or look for an updated app note on how
 to configure the values in this table for your board.
- Added support for the MGM240SA22VNA, BGM240SA22VNA, and BGM241SD22VNA modules and updated the configurations for the BGM240SB22VNA, MGM240SB22VNA, and the MGM240SD22VNA.

Improvements

Changed in release 3.5.2.0

Added new RAIL_ZWAVE_OPTION_PROMISCUOUS_BEAM_MODE to trigger RAIL_EVENT_ZWAVE_BEAM
on all beam frames.

Added RAIL_ZWAVE_GetBeamHomeldHash() to retrieve the beam frame's HomeldHash when handling that
event and made sure that the HomeldHash byte is now present on PTI for Z-Wave beam frames even when
Nodeld does not match.

Changed in release 3.5.1.0

- Corrected the sign of the frequency error reported by RAIL_GetRxFreqOffset() when using OFDM on the EFR32xG25 to match how this was handled for other modulations (e.g. Freq_error=current_freq-expected_freq).
- The RAIL_SetTune() and RAIL_GetTune() functions now use the CMU_HFXOCTuneSet() and CMU_HFXOCTuneSet() functions respectively on EFR32xG2x and newer devices.

Changed in release 3.5.0.0

- The RAIL_ConfigRfSenseSelectiveOokWakeupPhy() will now return an error when run on the EFR32xG21 platform because this device cannot support the wakeup PHY.
- Updated the pa_customer_curve_fits.py helper script to accept floating point value for the maximum power argument, similar to the increment argument.
- Added support in "RAIL Utility, Coexistence" component for configuring priority options when directional priority is enabled but no static priority GPIO is defined.
- Broke up some EFR32xG12 802.15.4 dynamic FEC code to save code size for Zigbee and Blluetooth LE, which
 never need this functionality.
- Remove "RAIL Utility, Coexistence" component dependency from the RAIL Utility, Coulomb Counter component.
- The RAIL_PrepareChannel() function has been made dynamic multiprotocol safe and will no longer return an error if called when your protocol is inactive.

Fixed Issues

Fixed in release 3.5.3.0

ID#	Description
1058480	Fixed an RX FIFO corruption on EFR32xG25 that occurred when receiving/sending certain OFDM packets using FIFO mode.
1109993	Fixed an issue in the "RAIL Utility, Coexistence" component so that it simultaneously asserts reque st and priority if request and priority share the same GPIO port and polarity.
1118063	Fixed issue with recent RAIL_ZWAVE_OPTION_PROMISCUOUS_BEAM_MODE on EFR32xG13 and xG14 where the Nodeld of the promiscuous beam was not properly recorded for RAIL_ZWAV E_GetBeamNodeld(), causing it to report 0xFF.
1126343	Fixed an issue on EFR32xG24 when using the IEEE 802.15.4 PHY where the radio could become stuck when doing an LBT transmit if a frame is received during the CCA check window.

Fixed in release 3.5.2.0

ID#	Description
747041	Fixed an issue on the EFR32xG23 and EFR32xG25 that could cause certain radio actions to delay for extended periods of time when the main core enters EM2 while the radio is still running.
1077623	Fixed an issue on EFR32ZG23 where multiple beam frames were lumped together on PTI as one I arge beam chain.
1090512	Fixed an issue in the "RAIL Utility, PA" component where certain functions would attempt to use the RAIL_TX_POWER_MODE_2P4GIG_HIGHEST macro even though they didn't support it. Previous ly this resulted in undefined behavior but will now correctly error.
1090728	Fixed a possible RAIL_ASSERT_FAILED_UNEXPECTED_STATE_RX_FIFO issue on EFR32xG12 with RAIL_IEEE802154_G_OPTION_GB868 enabled for a FEC-capable PH,Y which can happen when aborting a packet at frame detection, for instance by idling the radio.
1092769	Fixed an issue when using Dynamic Multiprotocol and BLE Coded PHYs where a transmit could underflow depending on what protocol was active when the PHY and syncword were loaded.
1103966	Fixed an unexpected Rx packet abort on the EFR32xG25 when using the Wi-SUN OFDM option4 MCS0 PHY.
1105134	Fixed an issue when switching certain PHYs that could cause the first received packet to be report ed as RAIL_RX_PACKET_READY_CRC_ERROR instead of RAIL_RX_PACKET_READY_SUCCESS. This issue could potentially impact EFR32xG22 and new er chips.
1109574	Fixed an issue on EFR32xG22 and newer chips where a radio sequencer assert could cause the a pplication to hang in an ISR rather than report the assert via RAILCb_AssertFailed().

Fixed in release 3.5.1.0

ID#	Description
1077611	Fixed an issue on the EFR32xG25 that would cause a 40 µs porch before an OFDM TX.
1082274	Fixed an issue on the EFR32xG22, EFR32xG23, EFR32xG24, and EFR32xG25 chips that could c ause the chip to lock up if the application attempted to re-enter EM2 within $\sim 10~\mu s$ after wake-up a nd hit a $< 0.5~\mu s$ timing window. If hit, this lockup required a power on reset to restore normal operat ion to the chip.

Fixed in release 3.5.0.0

ID#	Description
843708	Moved function declarations from rail_features.h to rail.h to avoid a convoluted include dependency order.
844325	Fixed RAIL_SetTxFifo() to properly return 0 (error) rather than 4096 for an undersized FIFO.
845608	Fixed an issue with the RAIL_ConfigSyncWords API when using certain underlying demodulator h ardware on EFR32xG2x parts.

ID#	Description
851150	Fixed an issue on EFR32xG2 series devices where the radio would trigger RAIL_ASSERT_SEQUENCER_FAULT when PTI is used and GPIO configuration is locked. GPIO configuration can only be locked when PTI is disabled. See RAIL_EnablePti() for further informatio n.
857267	Fixed an issue when using the "RAIL Utility, Coexistence" component with TX abort, the signal iden tifier feature and DMP.
1015152	Fixed an issue on EFR32xG2x devices where RAIL_EVENT_RX_FIFO_ALMOST_FULL or RAIL_EVENT_TX_FIFO_ALMOST_EMPTY could trigger improperly when the event is enabled or the FI FO is reset.
1017609	Fixed an issue where PTI appended information could be corrupted when RAIL_RX_OPTION_TRACK_ABORTED_FRAMES is in effect when RAIL_IDLE_FORCE_SHUTD OWN or RAIL_IDLE_FORCE_SHUTDOWN_CLEAR_FLAGS is used. Also clarified that RAIL_RX_OPTION_TRACK_ABORTED_FRAMES is not useful with coded PHYs.
1019590	Fixed an issue when using the "RAIL Utility, Coexistence" component with BLE where the sl_bt_system_get_counters() function would always return 0 for GRANT denied counts.
1019794	Eliminated compiler warning in "RAIL Utility, Initialization" component when few of its features are enabled.
1023016	Fixed an issue on EFR32xG22 and newer chips where waits in between radio activity would consume slightly more power than necessary after the first 13 ms. This was especially noticeable when using RAIL_ConfigRxDutyCycle with large off time values.
1029740	Fixed issue where RAIL_GetRssi()/RAIL_GetRssiAlt() could return a "stale" RSSI value (the value was from previous RX state instead of the current one) if called quickly upon entering receive.
1040814	Added support to the "RAIL Utility, Coexistence" component for configuring the coexistence reques t priority on sync detect when using BLE.
1056207	Fixed an issue with IQ sampling when using the "RAIL Utility, AoX" component with only 0 or 1 ant ennas selected.
1062712	Fixed an issue where the "RAIL Utility, Coexistence" component would not always update request states correctly, which could lead to missed events triggered by new requests.
1062940	Prevented the "RAIL Utility, Coexistence" component from aborting BLE transmits when SL_RAIL_UTIL_COEX_BLE_TX_ABORT is disabled.
1063152	Fixed an issue where radio reception would not be fully cleaned up when a receive error occured w ith receive state transitions set to idle on error but transmit on success, a configuration mostly asso ciated with BLE. On the EFR32xG24 this could cause a SYNTH calibration to not be properly resto red and eventually cause the radio to stop working.

Known Issues in the Current Release

Issues in bold were added since the previous release.

ID#	Description	Workaround
	Using direct mode (or IQ) functionality on EFR3 2xG23 requires a specifically set radio configuration that is not yet supported by the ra dio configurator. For these requirements, reach out to technical support who could provide that configuration based on your specification	
641705	Infinite receive operations where the frame's fix ed length is set to 0 are not working correctly on the EFR32xG23 series chips.	
732659	 On EFR32xG23: Wi-SUN FSK mode 1a exhibits a PER floor w ith frequency offsets around ± 8 to 10 KHz Wi-SUN FSK mode 1b exhibits a PER floor w ith frequency offsets around ± 18 to 20 KHz 	

Deprecated Items

None

Removed Items

None

Using This Release

This release contains the following

- Radio Abstraction Interface Layer (RAIL) stack library
- Connect Stack Library
- RAIL and Connect Sample Applications
- RAIL and Connect Components and Application Framework

This SDK depends on Gecko Platform. The Gecko Platform code provides functionality that supports protocol plugins and APIs in the form of drivers and other lower layer features that interact directly with Silicon Labs chips and modules. Gecko Platform components include EMLIB, EMDRV, RAIL Library, NVM3, and mbedTLS. Gecko Platform release notes are available through Simplicity Studio's Documentation tab.

For more information about the Flex SDK v3.x see UG103.13: RAIL Fundamentals and UG103.12: Silicon Labs Connect Fundamentals. If you are a first time user, see QSG168: Proprietary Flex SDK v3.x Quick Start Guide.

Installation and Use

The Proprietary Flex SDK is provided as part of the Gecko SDK (GSDK), the suite of Silicon Labs SDKs. To quickly get started with the GSDK, install Simplicity Studio 5, which will set up your development environment and walk you through GSDK installation. Simplicity Studio 5 includes everything needed for IoT product development with Silicon Labs devices, including a resource and project launcher, software configuration tools, full IDE with GNU toolchain, and analysis tools. Installation instructions are provided in the online Simplicity Studio 5 User's Guide.

Alternatively, Gecko SDK may be installed manually by downloading or cloning the latest from GitHub. See https://github.com/Sili-conLabs/gecko_sdk for more information.

Simplicity Studio installs the GSDK by default in

- (Windows): C:\Users\<NAME>\SimplicityStudio\SDKs\gecko_sdk
- (MacOS): /Users/<NAME>/SimplicityStudio/SDKs/gecko_sdk

Documentation specific to the SDK version is installed with the SDK. Additional information can often be found in the knowledge base articles (KBAs). API references and other information about this and earlier releases is available on https://docs.silabs.com/

Security Information

Secure Vault Integration


When deployed to Secure Vault High devices, sensitive keys are protected using the Secure Vault Key Management functionality. The following table shows the protected keys and their storage protection characteristics.

Wrapped Key	Exportable / Non-Exportable	Notes
Thread Master Key	Exportable	Must be exportable to form the TLVs
PSKc	Exportable	Must be exportable to form the TLVs
Key Encryption Key	Exportable	Must be exportable to form the TLVs
MLE Key	Non-Exportable	
Temporary MLE Key	Non-Exportable	
MAC Previous Key	Non-Exportable	
MAC Current Key	Non-Exportable	
MAC Next Key	Non-Exportable	

Wrapped keys that are marked as "Non-Exportable" can be used but cannot be viewed or shared at runtime. Wrapped keys that are marked as "Exportable" can be used or shared at runtime but remain encrypted while stored in flash. For more information on Secure Vault Key Management functionality, see AN1271: Secure Key Storage.

Security Advisories

To subscribe to Security Advisories, log in to the Silicon Labs customer portal, then select Account Home. Click HOME to go to the portal home page and then click the Manage Notifications tile. Make sure that 'Software/Security Advisory Notices & Product Change Notices (PCNs)' is checked, and that you are subscribed at minimum for your platform and protocol. Click Save to save any changes.



Support

Development Kit customers are eligible for training and technical support. Use the Silicon Labs Flex web page to obtain information about all Silicon Labs Thread products and services, and to sign up for product support. You can contact Silicon Laboratories support at http://www.silabs.com/support

Simplicity Studio

One-click access to MCU and wireless tools, documentation, software, source code libraries & more. Available for Windows, Mac and Linux!



- IoT Portfolio
 - www.silabs.com/loT
- SW/HW
 - www.silabs.com/simplicity
- Quality
 - www.silabs.com/quality
- Support & Community
 - www.silabs.com/community

Disclaimer

Silicon Labs intends to provide customers with the latest, accurate, and in-depth documentation of all peripherals and modules available for system and software imple-menters using or intending to use the Silicon Labs products.

Characterization data, available modules and peripherals, memory sizes and memory addresses refer to each specific device, and "Typical" parameters provided can and do vary in different applications. Application examples described herein are for illustrative purposes only. Silicon Labs reserves the right to make changes without further notice to the product information, specifications, and descriptions herein, and does not give warranties as to the accuracy or completeness of the included information. Without prior notification, Silicon Labs may update product firmware during the manufacturing process for security or reliability reasons. Such changes will not alter the specifications or the performance of the product. Silicon Labs shall have no liability for the consequences of use of the information supplied in this document. This document does not imply or expressly grant any license to design or fabricate any integrated circuits. The products are not designed or authorized to be used within any FDA Class III devices, applications for which FDA premarket approval is required or Life Support Systems without the specific written consent of Silicon Labs. A "Life Support System" is any product or system intended to support or sustain life and/or health, which, if it fails, can be reasonably expected to result in significant personal injury or death. Silicon Labs products are not designed or authorized for military applications. Silicon Labs products shall under no circumstances be used in weapons of mass destruction including (but not limited to) nuclear, biological or chemical weapons, or missiles capable of delivering such weapons. Silicon Labs disclaims all express and implied warranties and shall not be responsible or liable for any injuries or damages related to use of a Silicon Labs product in such unauthorized applications. Note: This content may contain offensive terminology that is now obsolete. Silicon Labs is replacing these terms with inclusive language wherever possible. For more information, visit www.silabs.com/about-us/inclusive-lexicon-project

Trademark Information

Silicon Laboratories Inc.®, Silicon Laboratories®, Silicon Labs®, Silabs® and the Silicon Labs logo®, Bluegiga®, Bluegiga Logo®, EFM®, EFM32®, EFR, Ember®, Energy Micro, Energy Micro logo and combinations thereof, "the world's most energy friendly microcontrollers", Redpine Signals®, WiSeConnect, n-Link, EZLink®, EZRadio®, EZRadioPRO®, Gecko®, Gecko OS, Gecko OS Studio, Precision32®, Simplicity Studio®, Telegesis, the Telegesis Logo®, USBXpress®, Zentri, the Zentri logo and Zentri DMS, Z-Wave®, and others are trademarks or registered trademarks of Silicon Labs. ARM, CORTEX, Cortex-M3 and THUMB are trademarks or registered trademarks of ARM Holdings. Keil is a registered trademark of ARM Limited. Wi-Fi is a registered trademark of the Wi-Fi Alliance. All other products or brand names mentioned herein are trademarks of their respective holders.

- · Silicon Laboratories Inc.
- 400 West Cesar Chavez Austin, TX 78701
- USA
- www.silabs.com

Documents / Resources



SILICON LABS SDK 3.5.6.0 GA Proprietary Flex Development Software [pdf] User Guide SDK 3.5.6.0 GA, SDK 3.5.6.0 GA Proprietary Flex Development Software, Proprietary Flex Development Software, Flex Development Software, Software

References

- Silicon Labs
- Silicon Labs
- About Us Silicon Labs
- Silicon Labs Community
- <a>Internet of Things (IoT) Silicon Labs
- Simplicity Studio Silicon Labs

- Et al. Technical Support Silicon Labs
- User Manual

Manuals+, Privacy Policy

This website is an independent publication and is neither affiliated with nor endorsed by any of the trademark owners. The "Bluetooth®" word mark and logos are registered trademarks owned by Bluetooth SIG, Inc. The "Wi-Fi®" word mark and logos are registered trademarks owned by the Wi-Fi Alliance. Any use of these marks on this website does not imply any affiliation with or endorsement.