


Tesla Inc 2022 Update Vehicle Software to Improve Steering Fee





Tesla Inc 2022 Update Vehicle Software to Improve Steering Fee User Guide

[Home](#) » [Tesla Inc](#) » Tesla Inc 2022 Update Vehicle Software to Improve Steering Fee User Guide 

Contents

- [1 Tesla Inc 2022 Update Vehicle Software to Improve Steering Fee](#)
- [2 Specifications](#)
- [3 Condition](#)
- [4 Correction](#)
- [5 Procedure](#)
- [6 Documents / Resources](#)
 - [6.1 References](#)



Tesla Inc 2022 Update Vehicle Software to Improve Steering Fee



Specifications

- Manufacturer: Tesla, Inc.
- Service Bulletin: SB-24-32-001
- Date: January 13, 2024
- Classification: Recall Bulletin
- Model Year/Model: 2022 – 2023 Model 3, Model Y
- Build Location: Giga Berlin, Giga Shanghai
- Region: Asia Pacific, Europe, Middle East

The model(s) and model year(s) listed are a general approximation of the affected VIN list. Refer to the VIN/Bulletin Tracker or Customer/Vehicle profile to determine the applicability of this bulletin for a particular vehicle.

Recall Bulletin: Recall Bulletins are mandatory service procedures that, unless they can be completed via a software update that a customer installs through the normal course of ownership, must be carried out by Tesla-certified Service Centers. Recall work performed by uncertified technicians could lead to unsafe conditions or voided warranty provisions.

Condition

On certain Model 3 and Model Y vehicles built between May 18, 2022, and September 13, 2023, the driver may experience a notchy feel or sensation from the steering wheel when operating the vehicle in cold temperatures, which may not comply with ECE Regulation R79, 5.1.1 and 5.1.2.

Correction

Inspect the vehicle software version, and if necessary, update the vehicle software to version 2023.38 or later.


Procedure

1. On the vehicle touchscreen, touch Controls (vehicle icon) > Software, and then scroll down to display the vehicle software version.

- If the vehicle is operating with software version 2023.38 or later, no further action is necessary. Use correction code S012432001.
- If the vehicle is operating with a software version earlier than 2023.38, update the software to version 2023.38 or later (refer to Service Manual procedure 00020003; Model 3, Model Y). Use correction code S022432001.

For feedback on the accuracy of this document, email ServiceBulletinFeedback@tesla.com

Documents / Resources

	<p>Tesla Inc 2022 Update Vehicle Software to Improve Steering Fee [pdf] User Guide 2022 Update Vehicle Software to Improve Steering Fee, 2022, Update Vehicle Software to Improve Steering Fee, Software to Improve Steering Fee, Improve Steering Fee, Steering Fee</p>
---	--

References

- [User Manual](#)

[Manuals+](#), [Privacy Policy](#)

This website is an independent publication and is neither affiliated with nor endorsed by any of the trademark owners. The "Bluetooth®" word mark and logos are registered trademarks owned by Bluetooth SIG, Inc. The "Wi-Fi®" word mark and logos are registered trademarks owned by the Wi-Fi Alliance. Any use of these marks on this website does not imply any affiliation with or endorsement.